





Test Report Page 1 of 2

Client: Witzenberg Municipality Date of report: 11 September 2024

Address:50 Voortrekker Street, Ceres, 6835Date accepted:02 September 2024Report no:195324Date completed:11 September 2024

**Project:** Witzenberg Drinking Water Date received: 02 September 2024

Lak	no:		Uncertainty of measure- ment %	SANS 241- 1:2015	127417		
Da	te samı	pled:			02-Sep-24		
Αq	uatico	sampled:			Yes		
Sar	nple ty	pe:			Water		
Loc	ality de	escription: Analyses			Ceres Reservoir Final Post Chlorination		
Α	AQCL	pH @ 25°C	pН	ALM 20	2.33	5 - 9.7	6.02
Α		Electrical conductivity (EC) @ 25°C	mS/m	ALM 20	4.92	< 170	5.48
Α	AQCL	Total Dissolved solids @ 180°C	mg/l	ALM 24	9.42	< 1200	42
Α	AQCL	Chloride (CI)	mg/l	ALM 02	7.57	< 300	8.27
Α	AQCL	Nitrate (NO₃) as N	mg/l	ALM 06	9.46	< 11	0.729
Α	AQCL	Total oxidised nitrogen as N	mg/l	ALM 06	9.46		0.737
Α	AQCL	Nitrite (NO <sub>2</sub> ) as N	mg/l	ALM 07	7.73	< 0.9	<0.065
Α	AQCL	Ammonium (NH <sub>4</sub> ) as N	mg/l	ALM 05	8.46	< 1.5	<0.008
N	AQCL	Un-ionized Ammonia as N	mg/l	ALM 26			<0.005
Α	AQCL	Fluoride (F)	mg/l	ALM 08	9.76	< 1.5	<0.263
Α	AQCL	Acid Soluble Aluminium (Al)	mg/l	ALM 31	7.08	< 0.3	0.098
Α	AQCL	Acid Soluble Iron (Fe)	mg/l	ALM 31	7.16	< 0.3	0.071
Α	AQCL	Acid Soluble Manganese (Mn)	mg/l	ALM 31	6.34	< 0.1	0.004
Α	AQCL	Acid Soluble Copper (Cu)	mg/l	ALM 31	5.15	< 2	<0.002
Α	AQCL	E.coli	CFU/100ml	ALM 40	7.74	0	<1
Α	AQCL	Total coliform	CFU/100ml	ALM 40	7.76	< 10	<1
Α	AQCL	Heterotrophic plate count	CFU/ml	ALM 43	2.22	< 1000	<1
Α	AQCL	Turbidity	NTU	ALM 21	5.9	< 1	6.74
N	AQCL	Total Chlorine (Cl₂)	mg/l	ALM 23	5.94		0.21
Α	AQCL	Free chlorine (Cl <sub>2</sub> )	mg/l	ALM 23	5.94	< 5	0.16
Α	AQCL	True Colour	mg/l Pt-Co	ALM 22	8.74	< 15	<5.00
Α	AQL	Total organic carbon (TOC)	mg/l	ALM 63	6.46	< 10	3.16
Α	AQCL	Temperature	°C	ALM 20			21.7
N	AQL	Nitrate + Nitrite as N	mg/l	ALM 26			0.737
Α	AQCL	Nitrite as NO <sub>2</sub>	mg/l	ALM 26			0.026

A = Accredited N = Non accredited Sub = Sub-contracted NR = Not requested RTF = Results to follow NATD = Not able to determine ATR = Alternative test report; Results relate only to the items sampled and tested; Results reported against the limit of detection; Results marked 'Non SANAS Accredited' in this report are not included in the SANAS Schedule of Accreditation for this laboratory; Uncertainty of measurement available on request for all methods included in the SANAS Schedule of Accreditation; The report shall not be reproduced except in full without approval of the laboratory

AQL = Aquatico Laboratories ; AQCL = Aquatico Cape Laboratories







Test Report Page 2 of 2

Client: Witzenberg Municipality Date of report: 11 September 2024

Address:50 Voortrekker Street, Ceres, 6835Date accepted:02 September 2024Report no:195324Date completed:11 September 2024

**Project:** Witzenberg Drinking Water Date received: 02 September 2024

Lak	no:		Uncertainty of measure- ment %	SANS 241- 1:2015	127417		
Da	te samı	oled:			02-Sep-24		
Αq	uatico s	sampled:			Yes		
Saı	mple ty	pe:			Water		
Loc	cality de	escription: Analyses			Ceres Reservoir Final Post Chlorination		
Α	AQCL	Nitrate as NO₃	mg/l	ALM 26			3.23
Α	AQL	Trihalomethanes (THM)	μg/l	OLM 02	12.24		91
Α	AQL	Bromoform	μg/l	OLM 02	11.28	< 100	<2
Α	AQL	Chloroform	μg/l	OLM 02	13.73	< 300	81
Α	AQL	Dibromochloromethane	μg/l	OLM 02	11.83	< 100	<2
Α	AQL	Bromodichloromethane	μg/l	OLM 02	12.11	< 60	9
Α	AQL	Combined Bromoform	ratio	OLM 02			<0.020
Α	AQL	Combined Chloroform	ratio	OLM 02			0.271
Α	AQL	Combined Dibromochloromethane	ratio	OLM 02			<0.020
Α	AQL	Combined Bromodichloromethane	ratio	OLM 02			0.156
Α	AQL	THM Sum of rations	ratio	OLM 02		< 1	0.427
N	AQL	Combined Nitrate plus Nitrite	ratio	ALM 26		< 1	<1.00
Α	AQCL	Free and Saline Ammonia as N	mg/l	ALM 26			<0.005

A = Accredited N = Non accredited Sub = Sub-contracted NR = Not requested RTF = Results to follow NATD = Not able to determine ATR = Alternative test report; Results relate only to the items sampled and tested; Results reported against the limit of detection; Results marked 'Non SANAS Accredited' in this report are not included in the SANAS Schedule of Accreditation for this laboratory; Uncertainty of measurement available on request for all methods included in the SANAS Schedule of Accreditation; The report shall not be reproduced except in full without approval of the laboratory

Authenticated signature on first page

AQL = Aquatico Laboratories ; AQCL = Aquatico Cape Laboratories